
Offsite Advisory

FREE GUIDE · 2026 EDITION

The Offsite guide to modern methods of construction (MMC) in Australia

What MMC is, where it fits, what to watch out for, and how to take your first project from idea to delivery.



For Australian construction companies, builders and developers

offsiteadvisory.com

WELCOME

Building differently starts with understanding the options.

Most Australian construction companies have heard about prefab, modular and 3D printed buildings. Far fewer have actually delivered a project that way.

That is not because the methods do not work. It is because the process is different: you are buying from a factory, sometimes overseas, and you need to get finance, engineering, certification, shipping and site works lined up in a new order.

This guide gives you a clear, practical overview of modern methods of construction (MMC) in the Australian market. It explains the main types, the real benefits, the risks that catch people out, and the steps we use to take a construction company through its first MMC project.

Use it to decide whether MMC is worth exploring for your next project, and what questions to ask before you commit.

BS

Ben Sinclair
Offsite Advisory

INSIDE THIS GUIDE

03 Why MMC, why now

04 What modern methods of construction actually are

05 The five main types of MMC

06 MMC compared with traditional building

07 The challenges nobody tells you about

08 Regulation and government support in Australia

09 Is MMC right for your project? A quick checklist

10 How Offsite Advisory helps

11 Our six-step process

12 Your next step, and sources

Who this guide is for

Builders, construction companies and developers in Australia who are considering prefabricated, modular, imported or 3D printed construction for the first time, or who want a more structured way of doing it.

KEY TERMS USED IN THIS GUIDE

MMC
Modern methods of construction: building approaches that move work off site or use new technology on site.

Prefab
Any building element made in a factory before it arrives on site.

Modular
Complete 3D modules, often fully fitted out, joined together on site.

3DCP
3D concrete printing: walls built layer by layer by a robotic printer.

NCC
National Construction Code: the minimum building standards in Australia.

ABCB
Australian Building Codes Board, which manages the NCC.

Why MMC, why now

Australia has committed to building more homes, faster, than the industry has delivered in decades. Traditional methods alone are struggling to keep up, and governments are now actively backing factory-built construction.

1.2M

new homes targeted under the National Housing Accord, by mid-2029

SOURCE 1

~1/4

of that target completed so far: around 308,000 homes, with the goal now projected to be reached in late 2030

SOURCE 2

<10%

of Australian construction uses prefab, according to prefabAUS, while an estimated 90% of Swedish houses are built this way


SOURCE 3

50%

faster: the Federal Government says homes can be built up to 50% faster using prefab and modular methods

SOURCE 4

National Housing Accord progress — around 308,000 of 1,200,000 homes



Completed so far (Source 2) — Still to build: around 892,000 homes

The gap is the opportunity

The shortfall between the homes Australia needs and the homes being built is not closing fast enough on its own. Labour shortages, weather delays and rising costs all push timelines out on traditional sites.

MMC moves a large part of the work into a controlled factory environment, where it can happen in parallel with site preparation. That is why state and federal governments are funding it, and why early adopters are building capability now.

What this means for your business

- ✓ Clients and developers are starting to ask for MMC options.
- ✓ Government housing programs increasingly favour faster delivery models.
- ✓ Companies that learn the process early gain a competitive edge.
- ✓ Getting the first project right sets up every project after it.

What modern methods of construction actually are

Modern methods of construction (MMC) is an umbrella term for ways of building that move work away from the building site and into a controlled environment, or that use new technology to build more efficiently on site.

Traditional construction

- Design
- Approvals
- Site works
- Structure on site
- Fit-out on site
- Handover

Each stage mostly waits for the one before it, and almost everything happens outdoors, exposed to weather and trade availability.

Modern methods of construction

- Design (fixed early)
- Approvals
- Factory build | Site works
- Delivery and install
- Handover

Factory production and site preparation happen at the same time. The building arrives largely complete and is installed in days or weeks.

Off site

Components, panels or whole modules are manufactured in a factory, in Australia or overseas.

On site, but different

Technologies like 3D concrete printing build the structure on site with far less manual labour.

Designed for assembly

Buildings are designed around how they will be made, shipped and put together, not just how they will look.

The key shift: with MMC, most of the big decisions are made **before** anything is built. That front-loading is where the time savings come from, and also where most first-time mistakes happen.

03 · THE OPTIONS

The five main types of MMC

MMC is not one thing. Each method suits different projects, budgets and sites. Many real projects combine two or more.

3D 01

Volumetric modular

Complete room-sized modules are built and fitted out in a factory, then transported and craned into place. Common for housing, accommodation, schools and site offices.

Highest level of off-site completion

2D 02

Panelised systems

Walls, floors and roofs are made as flat panels (timber frame, steel frame, SIPs or precast concrete) and assembled on site. Easier to transport than full modules.

Flexible design, efficient freight

COMPONENTS 03

Pods and sub-assemblies

High-value, repetitive parts such as bathroom pods, kitchen pods or plant rooms are made in a factory and dropped into a traditionally built structure.

Easy first step into MMC

IMPORTED 04

Flat pack and imported buildings

Factory-made buildings or kits sourced from manufacturers in countries such as China, Turkey and Vietnam, shipped in containers and assembled in Australia.

Cost-competitive, needs careful due diligence

ON SITE 05

3D concrete printing (3DCP)

A robotic printer builds walls layer by layer from a concrete mix. In Perth, the walls of a two-storey home were printed in under 18 hours, with the project finished in about five months (Source 5).

Fast structure, design freedom

Which one is right?

It depends on your building type, how repetitive the design is, site access, timeframes and budget. Choosing the method is one of the first things we work through with you.

04 · THE TRADE-OFFS

MMC compared with traditional building

MMC is not automatically better. It changes where the effort, risk and cost sit in a project. Here is an honest side-by-side.

	TRADITIONAL	MMC
Build time	Stages run one after another; weather delays are common	Factory and site work run in parallel; government estimates up to 50% faster
Cost certainty	Costs can move during the build as variations and delays add up	More cost is locked in at the design and factory contract stage
Quality	Depends heavily on site conditions and individual trades	Controlled factory conditions and repeatable processes
Waste	Offcuts and excess material are common on site	Materials are cut and ordered precisely, with less waste
Labour	Relies on skilled trades being available on site	Less on-site labour; more work done by factory teams
Site disruption	Long periods of noise, deliveries and activity	Shorter on-site period, fewer deliveries
Design changes	Changes possible later in the process	Design must be fixed early; late changes are costly
Cash flow	Payments usually follow progress on site	Deposits and factory payments are often needed upfront

The last two rows are where most first MMC projects run into trouble. They are not reasons to avoid MMC, but they need to be planned for from day one.

The challenges nobody tells you about

Most MMC projects that go wrong do not fail because of the building method. They fail because of the process around it.

01 Choosing the wrong manufacturer

Factories vary enormously in quality, capacity and experience with Australian requirements. A polished brochure is not a factory inspection.

02 Compliance and certification

Buildings must meet the National Construction Code (NCC) and relevant Australian Standards. Some imported products need specific engineering or certification before they can be used.

03 Finance that does not fit

Lenders are used to progress payments on site. Paying a factory deposit before anything is on site needs a different finance structure.

04 Engineering gaps

Footings, connections, wind and bushfire ratings, and services all need to work with the chosen system. These are often underestimated.

05 Logistics and importation

Shipping, customs, biosecurity, transport permits, cranes and site access all have to line up on the right day.

06 No one owns the whole process

Manufacturer, builder, engineer, certifier and financier each see their own part. Without oversight, problems fall between the gaps.

FIVE QUESTIONS TO ASK ANY MANUFACTURER

1. Have you supplied buildings to Australia before, and can we speak to those clients?
2. Which Australian Standards and NCC requirements do your products already meet, and how is that documented?
3. Can we inspect your factory and see a project in production?
4. What is your payment schedule, and what happens if the project is delayed?
5. What is included in your price, and what will we need to arrange locally?

Good news: every one of these risks can be managed if it is identified early. That is exactly what an independent advisor is for.

Regulation and government support in Australia

The policy environment for MMC in Australia is moving quickly. Here are the key developments to be aware of as of September 2026.

March 2025

$54 million federal package

The Federal Government announced $50 million in matched grants for states and territories to expand prefab and modular programs, plus $4 million to develop a national certification system for off-site construction (Source 6).

May 2026

$39.3 million for System 600

Funding to take System 600 national: an open-source standard that helps prefabricated components from different manufacturers connect without custom engineering (Source 7).

2026

National Voluntary Certification Scheme

The Australian Building Codes Board (ABCB) released draft rules for a scheme that would let prefab manufacturers certify their systems once, nationally, against the NCC. Consultation closed on 15 September 2026, with the scheme indicatively expected around mid-2028 (Source 8).

Ongoing

State programs

States are running their own initiatives. NSW, for example, has flagged work on a new MMC manufacturing facility and regulatory framework (Source 2). Western Australia has a $50 million Housing Innovation Fund backing modular manufacturing (Source 9).

What this means today

Until national certification is in place, compliance is still handled project by project, through engineers, certifiers and existing pathways. Knowing which pathway applies to your product and state is essential.

Please note

Policy details, funding and timelines change. Always confirm the current position with the relevant authority or your advisor before making decisions.

07 · SELF-ASSESSMENT

Is MMC right for your project?

Tick every statement that applies to the project you have in mind. It takes two minutes and gives you a useful starting point.

- [ ] Does the project have a repetitive or standardised layout (units, rooms, modules)?
- [ ] Is a faster completion date valuable to you or your client?
- [ ] Can the design be fixed early, before manufacturing starts?
- [ ] Is there suitable access for trucks and cranes to the site?
- [ ] Is the site remote, or is skilled labour hard to find in the area?
- [ ] Are weather delays a real risk for this project or location?
- [ ] Could you fund a deposit or factory payments before work reaches site?
- [ ] Is your team open to working with a factory as a key supplier?
- [ ] Is the project large enough, or part of a pipeline, to justify setting up the process?
- [ ] Would lower waste and a smaller site footprint help with approvals or neighbours?

7 TO 10 TICKS

Strong candidate. MMC is very likely worth a detailed assessment.

4 TO 6 TICKS

Worth exploring. A hybrid approach, such as pods or panels, may suit best.


0 TO 3 TICKS

Proceed carefully. MMC may still fit, but the business case needs testing first.

This checklist is a guide only. Every project is different, and we are happy to look at yours in more detail.

How Offsite Advisory helps


Offsite Advisory is an independent MMC consultancy for Australian construction companies. We sit on your side of the table and take you through the whole process, from finding the right manufacturer to finance, engineering, logistics, delivery and oversight.



TRADITIONAL CONSTRUCTION

Adding MMC to what you offer clients


You are a construction company considering MMC as part of your offer. We walk you through finding the right manufacturer, obtaining finance, engineering, logistics, delivery and oversight.



3D PRINTED CONSTRUCTION

Is your project right for 3D printing?

We advise on 3D printed construction and assess whether your project is suitable for 3D concrete printing (3DCP), drawing on direct industry experience.



PREFABRICATED AND IMPORTED

Sourcing prefabricated buildings

For manufacturers in China, Turkey, Vietnam and beyond, we carry out a full factory inspection, work out whether specific engineering is required, and check whether products need certifying to Australian standards. We also look at local prefabrication.

BS

Meet Ben Sinclair

Ben holds an MBA and has hands-on professional experience with modern construction systems, including 3D concrete printing. Through Offsite Advisory, he gives Australian construction companies independent, end-to-end guidance on bringing MMC into their projects.

09 · THE PROCESS

Six steps from first idea to final delivery

A clear, step-by-step process for a journey most construction companies have not made before. You can bring us in for the whole journey or for the steps where you need support most.

01. **Find the right manufacturer**

We identify and assess manufacturers in Australia and overseas, including a full factory inspection where the project calls for it.

Shortlist and comparison | Factory inspection | Capability and capacity check

02. **Secure finance**

We help you line up the finance an MMC project needs, including deposits and factory payments that happen before work reaches site.

Payment schedule review | Finance structure | Lender conversations

03. **Resolve the engineering**

We work out whether specific engineering is required, and whether the manufacturer's products need certifying to Australian standards.

NCC and standards review | Engineering scope | Certification pathway

04. **Plan the logistics**

We plan how the building or its components get from the manufacturer to your site, including importation.

Shipping and customs | Transport and permits | Crane and site access

05. **Manage delivery**

We coordinate delivery so the project arrives as planned and installation runs smoothly.

Delivery schedule | Site readiness | Install coordination

06. **Keep oversight to the end**

We stay involved to keep the project on track through to completion.

Progress checks | Issue resolution | Handover support

YOUR NEXT STEP

Ready to talk it through?

Tell us about your project and where you are with MMC today. We will come back to you with a clear view of your options. Every project is quoted directly.

Request a quote →

WEBSITE
www.offsiteadvisory.com

EMAIL
ben@offsiteadvisory.com

PHONE
+61 403 216 954 (Ben Sinclair)

SERVICE AREA
Nationwide, Australia

01

Tell us about your project

Send a quote request with the basics: location, building type, size and timing.

02

We talk it through

We look at where you are with MMC today and which methods could suit the project.

03

You receive a direct quote

A clear scope for the steps you need support with, quoted for your project.

Sources

1. Treasury, Delivering the National Housing Accord. treasury.gov.au/policy-topics/housing/accord
2. National Housing Supply and Affordability Council, Quarterly Report, August 2026. nhsac.gov.au
3. SBS News Dateline, "Like IKEA but for houses", April 2025 (updated July 2026), citing prefabAUS. sbs.com.au
4. Built Offsite, "Federal Government backs prefabrication and modular construction with $54 million boost", March 2025. builtoffsite.com.au
5. 3Dnatives, "Australia's first fully 3D printed two-storey home is completed", August 2025. 3dnatives.com
6. Built Offsite, as above (Source 4).
7. Prefab News, "Federal Government commits $39.3 million to open-source prefab housing system", May 2026. prefabnews.com.au
8. The Good Builder, "The prefab certification scheme has moved from idea to draft rules", 2026. thegoodbuilder.com.au
9. The Good Builder, "WA's $50M Housing Innovation Fund to supercharge modular manufacturing and home supply". thegoodbuilder.com.au

This guide provides general information only and does not constitute financial, legal, engineering or building compliance advice. Figures and policy details were current as at September 2026 and may change. Seek advice specific to your project before making decisions.

© 2026 Offsite Advisory. All rights reserved.